

1 With respect to Differential Settlement, L (in inches) is defined as a maximum distance of
 2 25 feet, or the lesser distance between settlement reference points or major structural
 3 elements such as columns. Consider both heave and settlement in the determination of
 4 differential settlement.

5 **2.52.7.4.1 Alaskan Way Viaduct**

6 Allowable deformation tolerances for settlement and other parameters are shown in Tables
 7 2-52.6 and 2-52.7:

8 Table 2-52.6 – Alaskan Way Viaduct Bents 92 through 121

	Alert Level	Maximum Level	Location
Transverse Differential Vertical Movement (inches)	0.75	1.00	Measured between ends of transverse crossbeams
Transverse Differential Horizontal Movement (inches)	0.35	0.50	Measured between bent column/footing pedestal interface
Longitudinal Differential Vertical Movement (inches)	0.35	0.50	Measured between ends of exterior longitudinal girders
Longitudinal Differential Horizontal Movement (inches)	0.35	0.50	Measured between bent column/footing pedestal interface
Total Bent Settlement (inches)	1.50	2.00	Measured at bent column/footing pedestal interface

9 Table 2-52.7 – Alaskan Way Viaduct Bents E121 through E130

	Alert Level	Maximum Level	Location
Transverse Differential Vertical Movement (inches)	0.35	0.50	Measured between ends of transverse crossbeams
Transverse Differential Horizontal Movement (inches)	0.35	0.50	Measured between adjacent bent column/pile cap interface
Total Bent Settlement (inches)	0.75	1.00	Measured at bent column/pile cap interface

10 **2.52.7.4.2 Group A Buildings – Using Compensation Grouting as**
 11 **Deformation Mitigation Measure**

12 Table 2-52.8 – Group A Buildings Using Compensation Grouting as Mitigation

	Maximum Level
Settlement or Heave (inches)	±0.5
Differential Settlement (inches)	L/600

13 **2.52.7.4.3 Group A Buildings – Other Grouting Deformation Mitigation**
 14 **Measures**

15 Table 2-52.9 – Group A Buildings Using Other Mitigation Measures

	Alert Level	Maximum Level
Settlement or Heave (inches)	0.5	0.75
Differential Settlement (inches)	L/600	L/400

16 **2.52.7.4.4 Group B Buildings**

17 Table 2-52.10 – Group B Buildings

	Alert Level	Maximum Level
Settlement or Heave (inches)	0.5	1.0
Differential Settlement (inches)	L/600	L/300

1 **2.52.7.4.5 Group A Other Structures**

2 Table 2-52.11 – Group A Other Structures

Structures	Alert Level	Maximum Level
	Settlement (inch)	Settlement (inch)
BNSF Railway Tunnel	0.75	1.0
Pike Street Adit	0.75	1.0
EBI	0.75	1.0

3 **2.52.7.4.6 Group B Other Structures**

4 Table 2-52.12 – Group B Other Structures

Structures	Alert Level	Maximum Level
	Settlement (inch)	Settlement (inch)
Seawall	0.75	1.0
Columbia Street Ramp	0.75	1.0
Seneca Street Ramp	0.75	1.0
Marion Street Pedestrian Bridge	0.75	1.0
Monorail	0.75	1.0

Battery Street Tunnel	Alert Level	Maximum Level
Settlement	0.75 inch	1.0 inch
Horizontal Movement	0.75 inch	1.0 inch

6
 7 **2.52.7.4.7 Other Structures (Streets, Sidewalks, etc. and Seattle Steam) and**
 8 **Utilities**

9 Table 2-52.13 – Ground Surface Settlement Limits for Other Structures
 10 (Streets, Sidewalks, etc. and Seattle Steam) and Utilities¹

Tunnel Reach	Station Number	Maximum Level Inches ²
S. King Street to Yesler Way	200+00 to 213+00	3.0
Yesler Way to Madison Street	213+00 to 218+00	2.0
Madison Street to Denny Way	218+00 to 279+00	1.0
Denny Way to North End	279+00 to 288+20	1.5

11 ¹Maximum heave for streets, sidewalks, and utilities shall be 1.0 inch.

12 ²As measured by near surface settlement points

13 **2.52.7.4.8 Deep Settlement Limits Based on Borehole Extensometer**
 14 **Readings**

15 For the purposes of establishing Action Plans, the maximum level shall be 4 inches of
 16 settlement measured at a deep extensometer anchor point (multiple position borehole
 17 extensometer, MPBX) at 5 feet above the tunnel crown at the centerline of the tunnel
 18 alignment.

19 **2.52.8 DEFORMATION MITIGATION METHODS**

20 The Design-Builder shall implement mandatory deformation mitigation measures for
 21 Group A structures and utilities. Mitigation methods include grouting (compensation or
 22 compaction) from the ground surface, grouting from within the Bored Tunnel, and
 23 structural strengthening for buildings.